

Airflow Experts, Inc

'Air Balance Solutions for Critical Spaces'

Qualification Submission

January, 2011

The document(s) contained herein are considered proprietary information for the exclusive use of customers of Airflow Experts, Inc. and government regulatory and/or inspection agencies. This document is not to be reproduced or allowed to be seen by competitors of Airflow Experts, Inc. Additional requests for this document are to be made to Airflow Experts, Inc.



P.O. Box 1079
Graham, NC 27253
Phone: 336-229-1470
Fax: 336-578-5378
Email: sales@airflowexperts.com

January 8, 2011

Airflow Experts, Inc (AEI) is a certified woman-in-business enterprise providing air balancing solutions for critical spaces. Founded in 2005, it operates along the east coast of the United States from Connecticut to Georgia. AEI employs NEBB-accredited Test and Balance Supervisors at offices in Graham, North Carolina and Lehigh Valley, Pennsylvania with a combined 40 years of air balancing field expertise; supported by a full complement of NEBB certified field technicians, they are equipped to handle the most demanding of air balancing projects.

Airflow Experts, Inc possesses a full complement of state-of-the-art test instrumentation and equipment with full NIST traceable calibration histories. AEI business approach is focused on providing the most complete and comprehensive level of service to customers in critical spaces. AEI personnel have extensive experience in the balancing of laboratories, cleanrooms and pharmaceutical production facilities. All AEI procedures are standardized to help ensure regulatory compliances, report forms are user-friendly while providing all relevant information necessary for adherence to project specifications and regulatory agencies.

AEI field test reports are collected electronically using handheld computers or PDA's and downloaded via cell phone to a web-based data service. This data is immediately available for review by the NEBB supervisor and can be released for customer access via any web-enabled PC. This cutting-edge process ensures expedient delivery of accurate and intelligible final reports.

AEI Services:

- Air Balancing
- Hydronic Balancing
- Duct Leakage Testing
- Blower Door Testing
- Mechanical Systems
- Commissioning
- Sound & Vibration Testing

Typical Customers:

- Laboratories
- Cleanrooms
- Pharmaceutical Manufacturers
- Biotech Facilities
- Medical Device Manufacturers
- Hospitals
- Universities & Schools
- Food Service Establishments
- Office Buildings
- Shopping Malls
- Convention Centers
- Assisted Care Facilities

'Air Balance Solutions for Critical Spaces'





P.O. Box 1079
Graham, NC 27253
Phone: 336-229-1470
Fax: 336-578-5378
Email: sales@airflowexperts.com

Sample Client List

Cogenesys	Sandoz Pharmaceuticals
TEVA Biopharmaceuticals USA	MacroGenics
American Industrial Contractors	Charles River Laboratories
Chilsholm Services	Imclone Systems, Inc
GlaxoSmithKline	PPL Company
Merck West Point	PTC Therapeutics
Cardinal Health Systems	Air Energy Systems
Novartis Pharmaceuticals	University of North Carolina
Guildford Pharmaceuticals	N. C. State Bureau of Investigations
Global Pharmaceutical Supply Group	AeroPharm Technologies
Tengion, Inc.	Baxter Laboratories
Musculoskeletal Transplant Foundation	Lomax Construction
Genesis Engineers	Abbott Laboratories
National Institute of Health	University of North Carolina
LifeCell Technologies	Qiagen, Inc
Johnson & Johnson	Worth & Company
Ortho-Clinical Diagnostics	Dual Temp, Inc
MedImmune Incorporated	AERAS Global
Siemens Building Technologies	American Red Cross
Integrated Project Services	GE Healthcare
Talecris Plasmaspheres	Invitrogen
Elon University	Alamance Community College
Palram Incorporated	Dansko Incorporated
Lafayette College	West Chester University
BioReliance Corporation	America on Wheels
Whiting-Turner Contracting	DPT Laboratories
Grandview Hospital	St. Luke's Hospital
Goddard School	Lehigh University
Sanaria Incorporated	Immunomedics, Inc
Ursinus College	Tetralogics Incorporated
Honda Aero	Vertis Logistics
DJ Wagner Inc	HondaJet
United Mechanical Services	Womack Army Hospital
Northampton Area School District	Great Wolf Lodge
D'Huey Engineers	Haemonetics, Inc.
Osteotech, Inc.	Pfizer, Inc.
United States Navy	Taconic Biotechnology
UGI Utilities Corporation	Wake Forest University
West Pharmaceuticals	Yonkers Construction

Air Balancing

- ☐ Testing and Adjusting of Air Distribution Systems
- ☐ Adjusting Total System to Provide Design Quantities
- ☐ NEBB Certified Air Balance
- ☐ Electrical Measurements
- ☐ Establishing Quantitative Performance of All Equipment
- ☐ Verifying Automatic Controls
- ☐ Checking Installations for Conformity to Design
- ☐ Measuring and Establishing Fluid Quantities
- ☐ Recording and Reporting the Results


Hydronic Balancing

- ☐ Balancing of Water Flow Rate
- ☐ NEBB Certified Hydronic Balancing
- ☐ Circulating Pumps
- ☐ Electrical Measurements
- ☐ Calculating Energy Transfer Rates of Fluids Through Heat Exchangers
- ☐ Establishing Pressure Drop Relationships of Hydronic Components
- ☐ Ensuring Efficient Operation of Heating & Cooling Systems

Supplemental Services

- ☐ Sound Source Testing
- ☐ Noise Level Testing
- ☐ A&C Weighted Sound Measurements
- ☐ Octave Band Analysis
- ☐ Vibration Testing
- ☐ Vibration Source Identification
- ☐ Vibration Isolation
- ☐ Dynamic Balancing
- ☐ HVAC Commissioning
- ☐ Duct Leakage Testing

National Environmental Balancing Bureau



Recertification

THIS IS TO CERTIFY THAT
Airflow Experts, Inc.

in Graham, NC

HAS MET ALL REQUIREMENTS FOR RENEWAL OF NEBB
CERTIFICATION IN THE FOLLOWING DISCIPLINE

Air & Hydronics Systems

FOR THE BOARD OF DIRECTORS:


President


President-Elect

Exp. March 31, 2013


Airflow Experts, Inc./NC

No. 3336

NEBB Cert. No.



National Environmental Balancing Authority



Recertification

THIS IS TO CERTIFY THAT

Airflow Experts, Inc.

in Graham, NC

HAS MET ALL REQUIREMENTS FOR RENEWAL OF NEBB
CERTIFICATION IN THE FOLLOWING DISCIPLINE

Building Systems Commissioning

FOR THE BOARD OF DIRECTORS:

Exp. March 31, 2013

Airflow Experts, Inc./NC

No. 3336

NEBB Cert. No.



President



President-Elect

President-Elect



National Environmental Balancing Board



Recertification

THIS IS TO CERTIFY THAT

Airflow Experts, Inc. - Lehigh Valley, PA
in Lehigh Valley, PA

**HAS MET ALL REQUIREMENTS FOR RENEWAL OF NEBB
CERTIFICATION IN THE FOLLOWING DISCIPLINE**

Air & Hydronics Systems

FOR THE BOARD OF DIRECTORS:

Exp. March 31, 2013

Airflow Experts, Inc. - Lehigh Valley, PA/PA

No. 3369

NEBB Cert. No.

J. Doyle P.E. signs

President

Dorey S. S. S.

President-Elect

Candy Hatfield Clarke

Experience

2006 - Current Airflow Experts Graham, NC

Owner, Office Manager, Bookkeeper

- All office aspects while building company.
- Supporting techs in both Pennsylvania and North Carolina.
- Building/Sales North Carolina region.
- Suggested new products that increased earnings by 23%.

1999 - 2005 SAP America Newtown Square, PA

Telecommunications Systems Engineer III

- Maintain and support 20 remote sites: both PBX and Phonemail.
- Billing and System auditor for the telecommunications department.

1998 - 1999 NCIC Greensboro, NC

Integrations Consultant

- Multiple consultant assignments for: Telecommunications and computer network design and implementation, telecomm MAC support.

1996 - 1998 Burlington Insurance Co. Burlington, NC

Help Desk and Telecomm Support

- Maintain the Help Desk for both computer and telephone support.
- Provide software and hardware support for entire employee base of 100+ users.

1995 – 1996 CCCS Charleston, SC

Independent Contractor for Bosch Corp – Technology Specialist

1992 – 1995 Coastal Truck Parts and Driveline Myrtle Beach, SC

Owner/Bookkeeper

1988 – 1992 CIBA-Geigy Corp Greensboro, NC

Programmer Analyst

Education

1986-1989 Sandhills Community College Southern Pines, NC

- Associate Degree – Computer Engineering Applications Technology.
- Graduated with honors.

Interests

Working outside, helping with Hospice and spending time with family.

Donald James Clarke

Qualifications & Experience

Work Experience:

May 2005 to Present:

- Operations Manager for Airflow Experts, Inc.
- Responsible for all air balancing activities.
- Training and evaluation of balancing technicians.

November 1999 to May 2006: Employed by Micro-Clean, Inc. of Bethlehem, PA as *Balancing Division Manager*. Duties include:

- Creation and management of balancing services division within Micro-Clean, Inc.
- Establish standardized operating procedures (SOP's) for balancing activities.
- Training and evaluation of balancing technicians.
- Increased department revenue to 1.2 Million with 40% net margin in fiscal 2003.

September 1993 to October 1999: Employed by MCM TAB & Commissioning of Blaine, Washington as, *Project Engineer & Operations Manager*. Duties included;

- Testing, Adjusting & Balancing of HVAC Systems.
- Commissioning of Building Mechanical Systems.
- Supervision and daily work assignment of field technicians.
- Training and evaluation of field personnel.

July, 1992 to August, 1993: Employed By E.H. Price Limited in Surrey, British Columbia, as *Engineering Representative*. Duties included;

- Promoting air distribution products to engineering consultants.
- Technical support and literature distribution.
- Estimation and project cost control.
- Outside sales for Vancouver Island territory.

January 1990 to December, 1991: Employed By the Iron Ore Company of Canada in Labrador City, Newfoundland, as *Co-op Engineer*. Duties included; daily supervision and work assignment of a crew of tradespersons performing routine and preventative maintenance on iron ore processing equipment, updating CAD drawings of piping systems within the pellet plant, and engineering design of improvements to iron ore processing equipment.

April to August 1987: Employed by Newfoundland Hydro, in Bay D'Espoir, Newfoundland, as *Co-op Engineer*. Duties included; assisting the plant engineer Trevor Arbuckle, weekly vibration analysis of hydro-electric generating equipment, and feasibility assessment of replacing non-critical bearings with an engineered polymer.

Education:

1985 to 1992: Attended Memorial University of Newfoundland. Received a Bachelors Degree in Mechanical Engineering (Co-op Program). Cumulative average 77 %, GPA 2.2 out of 3.0.

1981 to 1985: Attended Botwood Senior High School. Graduated at the top of a class of 130. Cumulative average 92 %. Graduation with honors.

Certifications and Achievements:


Test, Adjust and Balance Supervisor, accredited by National Environmental Balancing Bureau, (NEBB) for air & hydronic environmental systems.

Associate Member of American Society of Heating Refrigeration and Air-conditioning Engineers (ASHRAE), Chairman of National Technical Committee TC 1.2 – Instruments and Measurements, and Secretary for Lehigh Valley ASHRAE Chapter.

Primary Researcher for ASHRAE funded Research Project 1212-RP entitled "Airflow Measurement of Biological Safety Cabinets" valued at \$95,000



National Environmental Balancing Institute



Recertification

THIS IS TO CERTIFY THAT

Donald James Clarke

with Airflow Experts, Inc. in Graham, NC

**HAS MET ALL THE NEBB REQUIREMENTS FOR
NEBB CERTIFIED PROFESSIONAL STATUS IN**

Hi & Hydronics Systems

FOR THE BOARD OF DIRECTORS:



President

Exp. March 31, 2013
Airflow Experts, Inc./NC

No. 3336

NEBB Cert. No.



President-Elect



National Environmental Balancing Authority



Recertification

THIS IS TO CERTIFY THAT

Donald James Clarke

with Airflow Experts, Inc. in Graham, NC

HAS MET ALL THE NEBB REQUIREMENTS FOR
NEBB CERTIFIED PROFESSIONAL STATUS IN

Building Systems Commissioning - Green Buildings

FOR THE BOARD OF DIRECTORS:



President

Exp. March 31, 2013

Airflow Experts, Inc./NC

No. 3336


NEBB Cert. No.



President-Elect



National Environmental Balancing Bureau



Recertification

THIS IS TO CERTIFY THAT

Donald James Clarke

with Airflow Experts, Inc. in Graham, NC

HAS MET ALL THE NEBB REQUIREMENTS FOR
NEBB CERTIFIED PROFESSIONAL STATUS IN

Building Systems Commissioning - HVAC AC

FOR THE BOARD OF DIRECTORS:



President

President

Exp. March 31, 2013

Airflow Experts, Inc./NC

No. 3336

NEBB Cert. No.



President-Elect

President-Elect

DAVID GATEWOOD JR. QUALIFICATION & EXPERIENCE

Highlights:

- Hand-selected by the Mid-Atlantic Environmental Balancing Bureau's Board of Directors to Co-Chair the Technical Committee for NEBB.
- Test, Adjust and Balance supervisor, certified by the National Environmental Balancing Bureau, (NEBB) for air and hydronic systems.

Work Experience:

May 2006 to Present: Employed by Airflow Experts of Graham, N.C. as Project Manager.

- Testing, adjusting and balancing of Air and Hydronic systems
- Responsible for ensuring that heating and air conditioning and ventilation (HVAC) systems are balanced according to specifications.
- Provide troubleshooting for difficult balance situations and offer possible solutions to Engineers and Mechanical Contractors.

May 2003 to Present: Employed by Micro Clean, Inc. of Bethlehem, PA as Project Manager.

- Supervision and daily work assignment of field technicians.
- Training and evaluation of field personnel.
- Responsible for ensuring that heating and air conditioning and ventilation (HVAC) systems are balanced according to specifications.
- Provide troubleshooting for difficult balance situations and offer possible solutions to Engineers and Mechanical Contractors.

June 2002 to May 2003: Employed by TAB Services Co, as Balancing Supervisor.

- Testing, Adjusting & Balancing of HVAC Systems.
- Responsible for training and managing balancing technicians.
- Commissioning of Building Mechanical Systems.
- Ensure that all budget requirements are met.

July 2001 to June 2002: Employed by Double T Balancing Co, as Balancing Supervisor.

- Testing, Adjusting & Balancing of HVAC Systems.
- Responsible for training and managing balancing technicians.

- Responsible for ensuring that HVAC are balanced according to specifications.
- Ensure that all budget requirements are met.

November 1994 to July 2001: Employed by Robinson Mechanical Co, as Balancing Technician/Supervisor & Journeyman Serviceman.

- Managed large balancing contracts.
- Expertise in technical services provided in HVAC systems.
- Control systems installation (DDC).
- Troubleshoot and maintain large commercial boiler systems and chiller plants.

September 1974 to October 1994: Employed by US Air Force

- Retrocommissioning - High-level technician providing critical time response service worldwide for troubleshooting and repair of HVAC systems beyond local technicians' capability level.
- Performed technical systems design compliance inspections throughout the Air Force on new facility HVAC systems prior to Air Force acceptance.
- Provided formal classroom technician training in Testing and Balancing.
- Investigated, identified and corrected numerous problems with buildings having indoor air quality issues.

Education:

1985 to 1989 Attended Community Collage of the Air Force, Gunter AFB, GA
Received an Associate Degree in:

Major: Applied Science

Minor: Heating and Air Conditioning and Electrical



National Environmental Balancing Bureau



Recertification

THIS IS TO CERTIFY THAT

David M. Gatewood, Jr.

with Airflow Experts, Inc. - Lehigh Valley, PA in Lehigh Valley, PA

HAS MET ALL THE NEBB REQUIREMENTS FOR
NEBB CERTIFIED PROFESSIONAL STATUS IN

Air & Hydronics Systems

FOR THE BOARD OF DIRECTORS:

Exp. March 31, 2013

Airflow Experts, Inc. - Lehigh Valley, PA/PA

No. 3369

NEBB Cert. No.

Stephen P. W.iggins

President

David M. Gatewood, Jr.

President-Elect

JAMES J. BATES

Qualifications and Experience

Experience

2006-Present Airflow Experts

AIR BALANCE TECHNICIAN

- Testing, Adjusting and Balancing of Environmental Systems
- Balancing of Cleanrooms and Controlled Environments
- Adjusting and Balancing of Laboratory Ventilation Systems
- NEBB certified Air Balance Technician

2000-2006 Micro-Clean, Inc.

AIR BALANCE TECHNICIAN

- Testing, Adjusting and Balancing of Environmental Systems
- Balancing of Cleanrooms and Controlled Environments
- Adjusting and Balancing of Laboratory Ventilation Systems
- NEBB certified Air Balance Technician

1997–2000 Ron Lenz Heating and Air Conditioning Beach Lake , PA

INSTALLER/SERVICE TECHNICIAN

- Installed residential and light commercial air conditioning
- Installed heating equipment
- Preventive maintenance

1996-1997 Shaunessy Heating & Air Conditioning Honesdale , PA

INSTALLER

- Installed residential air conditioning
- Installed commercial air conditioning
- Installed heating equipment.

1993-1996 Grandstyle Picture Frame Honesdale , PA

BUSINESS PARTNER

- Accounts payable, Accounts receivable.
- Dealing with sales representatives.
- Overseeing everyday business.
- Marketing new products.
- Inventory
-

Education

Dec 2000 – June 2001 Micro-Clean, Inc – Air Balance Training Course

- 250 Hours of Classroom Theory
- 1000 Hours of On the job training

1999 – 2000 HVAC Course (Lackawanna Career Institute)

- Universal EPA Certification

1989-1992 Cleveland Institute of Electronics

- Correspondence course
- Diploma in basic electronic theory


NATIONAL ENVIRONMENTAL BALANCING BUREAU

Certificate of Technician Recertification

James Bates

with

Airflow Experts, Inc. - Lehigh Valley, PA



has recertified as a

NEBB Testing, Adjusting and Balancing (TAB) Technician
for Air and Hydronic Environmental Systems

J. Doyle R.W. signed
NEBB President

January 30, 2011
Date

March 31, 2013
Expiration Date

Robert McManis
Chapter President

2/23/11
Date



Edward Petruno


Qualifications

Experience	<p>2007-Present Airflow Experts Air Balance Technician</p> <ul style="list-style-type: none">- Testing, Adjusting and Balancing of Environmental Systems- NEBB certified Air Balance Technician- Balancing: Clean Rooms, Schools, Controlled environments <p>2003-2006 Micro-Clean Inc Air Balance Technician Trainee/Assistant 7/03 – 5/05 Field Tech Level 1 5/05 – 7/06</p> <ul style="list-style-type: none">- Testing, Adjusting and Balancing Training/Assistance- Balancing: Clean Rooms, Schools and other controlled environments
Training	<ul style="list-style-type: none">- NEBB Procedural Standards and Certification- OSHA training: Hazard Communication, Ladder Safety, Fall Protection, Lockout/Tagout Standard, Fire Extinguisher, Aerial Work Platform, Bloodborne Pathogen Exposure Control Plan- Environmental Engineering Consultants Training Course for Testing and Balancing HVAC Systems 451
Education	<p>Two year certificate in Electronic Technology: Lehigh Carbon Community College</p>

NATIONAL ENVIRONMENTAL BALANCING BUREAU

Certificate of Technician Certification

Edward Petruno
with
Airflow Experts, Inc.



has certified as a
NEBB Testing, Adjusting and Balancing (TAB) Technician
for Air and Hydronic Environmental Systems

[Signature]

NEBB President

April 5, 2011

Date

March 31, 2013

Expiration Date

[Signature]

Chapter President

April 20, 2011

Date





Airflow Experts
STANDARD OPERATING PROCEDURES
BALANCING SERVICES
ALL (AEI) SOP'S ON A FOUR-YEAR REVIEW SCHEDULE

CURRENT SOP #	DESCRIPTION	IMP. DATE	CURRENT DATE	REVIEWER*	CUSTODIAN	REVIEW DATE
MOSA-0506 AEI	MINIMUM OUTSIDE AIR	Jan-00	May 25, 2006	OM/Pres/TC	CLARKE	May-11
EM-0506 AEI	ELECTRICAL MEASUREMENTS	Jan-00	May 25, 2006	OM/Pres/TC	CLARKE	May-11
RM-0506 AEI	ROTATIONAL MEASUREMENTS	Jan-00	May 25, 2006	OM/Pres/TC	CLARKE	May-11
CVSP-0506 AEI	CONSTANT VOLUME STATIC PRESSURES	Jan-00	May 25, 2006	OM/Pres/TC	CLARKE	May-11
VVSP-0506 AEI	VARIABLE VOLUME STATIC PRESSURES	Jan-00	May 25, 2006	OM/Pres/TC	CLARKE	May-11
TAD-0506 AEI	TERMINAL AIR DEVICES	Apr-01	May 25, 2006	OM/Pres/TC	CLARKE	May-11
DT-0506 AEI	DUCT TRAVERSES	Jan-01	May 25, 2006	OM/Pres/TC	CLARKE	May-11
RPD-0506 AEI	ROOM PRESSURE DIFFERENTIALS	Jul-01	May 25, 2006	OM/Pres/TC	CLARKE	May-11



*Pres- President; OM-Oper Mgr; TC- Technical Coordinator;



Instrument calibration

Serial No.	Manufacturer	Model	Calibration Date	Calibration Due
Tachometer				
1835670	Monarch	Pocket Laser Tach 200	29 Jul 10	28 Jul 11
C1280399	Shimpo	DT-205L	23 Jan 11	22 Jan 12
C2980070	Shimpo	DT-205L	21 Aug 10	20 Aug 11
C4880055	Shimpo	DT-205L	05 Feb 10	04 Feb 11
COAB0392	Shimpo	DT-205L	13 Apr 10	12 Apr 11
D5280102	Shimpo	DT-207L	05 Jun 10	04 Jun 11
G050486	Shimpo	DT-205L	03 Sep 10	02 Sep 11
New Inst		New Instrument		

Hydronic Multimeter

	70725158	Alnor	HM 670	05 Mar 10	04 Mar 11
	70750160	Alnor	HM 670	10 Feb 10	09 Feb 11
	70750161	Alnor	HM 670	08 Dec 10	07 Dec 11
	70915036	Alnor	HM 670	14 Apr 10	13 Apr 11
	70931051	Alnor	HM 670	20 Aug 10	19 Aug 11
	W03013	Shortridge	HDM-300	05 Jun 10	04 Jun 11
	W05025	Shortridge	HDM-300	13 Apr 10	12 Apr 11

Clamp-On Ammeter

	75860514	Fluke	89 IV	21 Aug 10	20 Aug 11
	78710854	Fluke	335	08 May 10	07 May 11
	79801976	Fluke	335	13 Apr 10	12 Apr 11
	88105714	Fluke	335	23 Jan 11	22 Jan 12
	92857329	Fluke	337	21 Aug 10	20 Aug 11
	94860231	Fluke	902	05 Jun 10	04 Jun 11
	95060148	Fluke	902	05 Jun 10	04 Jun 11
	99820044	Fluke	902	02 Sep 10	01 Sep 11


Thermoanemometer / Manometer

	00080337	TSI	8386	02 Sep 10	01 Sep 11
	01040113	TSI	8386	18 Aug 10	17 Aug 11
	01040114	TSI	8386	07 Oct 10	06 Oct 11
	01040132	TSI	8386	23 Jan 11	22 Jan 12
	02040115	TSI	8386	25 Nov 10	24 Nov 11
	02120175	TSI	8386	18 Nov 10	17 Nov 11
	03120135	TSI	8345	21 Aug 10	20 Aug 11
	306100	TSI	8355	02 Sep 10	01 Sep 11
	AVM430926003	Alnor	AVM430-A	25 Jun 10	24 Jun 11
	Q421223	Extech	407119A	21 Aug 10	20 Aug 11

Rotating Vane Anemometer

	03030219/03030220	TSI	8324 w/ 802149	23 Jan 11	22 Jan 12
	03040092/03040093	TSI	8324 w/ 802149	24 Nov 10	23 Nov 11
	04027179/04027180	ALNOR	RVD & 100 mm head	18 Nov 10	17 Nov 11
	54120083/54120084	TSI	8324 w/ 802149	13 Apr 10	12 Apr 11

Sound Level Meter

	3603A 234C16	Ivie Technologies	IE-33	13 Feb 10	12 Feb 11
	4104A804C16	Ivie Technologies	IE-33	23 Apr 10	22 Apr 11

Digital Balometer

	70745006	Alnor	6200D	18 Nov 10	17 Nov 11
	90826015	Alnor	EBT721	05 Jun 10	04 Jun 11
	90835040	Alnor	EBT721	21 Aug 10	20 Aug 11
	90932023	Alnor	EBT721	13 Aug 10	12 Aug 11
	M01465	Shortridge	ADM-870	29 Oct 10	28 Oct 11
	M03714	Shortridge	ADM-870C	14 Jan 11	13 Jan 12
	M04800	Shortridge	ADM 870C	18 Nov 10	17 Nov 11
	M04816	Shortridge	ADM-870C	23 Jan 11	22 Jan 12

Temperature Meter

	90824074	Alnor	AL72-T1	05 Jun 10	04 Jun 11
	CT021406026	Cooper Instruments	SH66AG	21 Aug 10	20 Aug 11

Pressure and Flow Gauge

	1885-4-700	The Energy Conservatory	DG-700	30 Jun 10	29 Jun 11
	96700033	Fluke	922	21 Aug 10	20 Aug 11
	97600066	Fluke	922	05 Jun 10	04 Jun 11
	97600069	Fluke	922	05 Jun 10	04 Jun 11
	97600070	Fluke	922	05 Jun 10	04 Jun 11
	98040146	Fluke	922	05 Jun 10	04 Jun 11
	99560102	Fluke	922	02 Sep 10	01 Sep 11

Temperature/Humidity Meter

	050109014	Cooper Instrument	SRH77A	02 Sep 10	01 Sep 11
	483656	Cooper Instrument	SRH77A	21 Aug 10	20 Aug 11
	90825020	Alnor	800189	05 Jun 10	04 Jun 11
	90832039	Alnor	800189	21 Aug 10	20 Aug 11



P.O. Box 1079
Graham, NC 27253
Phone: 336.229.1470
Fax: 336.229.1422
Email: sales@airflowexperts.com

Air and Hydronic Balance Report

**Sample Balancing Report
100 Main Street
Hometown
USA**

January 2011

Prepared for:

Joe's Plumbing & Heating
100 King Street
Smithfield
USA

TABLE OF CONTENTS

Project: Sample Balancing Report

<u>Report</u>	<u>System/Unit</u>	<u>Page #</u>
Cover Page		1
Table of Contents		2
Certification		3
Project Summary	SAMPLE	4
Air Handling Unit	AHU-1	5
Static Pressures	AHU-4	7
Duct Traverse Square Duct	AHU-1 / Supply	9
Air Outlet	AHU-1 / Supply Air	8
Air Apparatus	FC-3	10
Terminal Air Device	FC-4 / SUPPLY	11
Duct Traverse Round Duct	EF-1 / Exhaust	12
Terminal Air Valves	EF-1	13
Fan	EF-2	14
Terminal Air Device	VAV-1 / Supply	15
Exhaust Fan	EF-1	16
Fume Hood Face Velocity	EF-2	18
Room Pressure Differentials	ROOM TO AMBIENT	19
Room Pressure Differentials	ROOM TO ROOM	20
Other	ROOM AIR CHANGES PER HOUR	21
Chilled Water Cooling Coil	CC-1	22
Coil Apparatus	COOLING COIL CC-1	23
Hydronic Pump	New Report 31	
Valve	New Report 30	
Hydronic Circulating Pump	CHP-1	24
Room Pressure	Copy of New Report 438 / Sub-System 438	
Balancing Valve/Flow Meter	Hot Water Coils / Sub-System	25
Balancing Valve/Flow Meter	Hot Water Heating / 2nd Floor	26
Certificates		27



P.O. Box 1079
Graham, NC 27253
Phone: 336.229.1470
Fax: 336.229.1422
Email: sales@airflowexperts.com

CERTIFICATION

PROJECT: Sample Balancing Report

ADDRESS: 100 Main Street
Hometown
USA

The data presented in this report is an exact record of system performance and was obtained in accordance with NEBB standard procedures. Any variances from design quantities, which exceed NEBB tolerances, are noted throughout this report.

The air distribution systems have been tested & balanced and final adjustments have been made in accordance with NEBB "PROCEDURAL STANDARDS FOR TESTING, ADJUSTING, BALANCING OF ENVIRONMENTAL SYSTEMS" and the project specifications.

NEBB TAB FIRM: Airflow Experts Inc.

REG. NO.: 3336

CERTIFIED BY: Jim Clarke

DATE: January 8, 2011

The hydronic distribution systems have been tested & balanced and final adjustments have been made in accordance with NEBB "PROCEDURAL STANDARDS FOR TESTING, ADJUSTING, BALANCING OF ENVIRONMENTAL SYSTEMS" and the project specifications.

NEBB TAB FIRM: Airflow Experts Inc.

REG. NO.: 3336

CERTIFIED BY: Jim Clarke

DATE: January 8, 2011

SUBMITTED AND CERTIFIED BY:

NEBB TAB FIRM: Airflow Experts Inc.

TAB SUPERVISOR: Jim Clarke

SIGNATURE:



DATE: January 8, 2011



Phone: 888.229.1477
Fax: 888.229.0422



Project Summary

This form is used to summarize the results of the balancing activities, highlight any difficulties encountered, define system operating parameters during testing activities and identify any items which deviate from specified values. This area also identifies the primary contact for the project and whom to contact with any questions.



UNIT #
AHU-1

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

Constant Volume Air Handling Unit

Unit Number: AHU-1

Location: Mechanical Room

Service: Cleanroom

Manufacturer: Great Fan Co.

Model: 123456

Serial: 98765

Heating Device: Hot Water Coil

Cooling Device: Chilled Water Coil

Supply Fan Data

Fan Type: FCBI-DW

Fan Size: 25

Manufacturers; Fan: Fan & Fan, Inc

Motor: Electric Company

Specified Motor HP: 25

Nameplate: 30

Specified Motor RPM: 1800

Nameplate: 1725

Specified Motor
Volts: 480

Nameplate: 460

Motor Sheave Size: 2B50

Bushing: H1

Fan Sheave Size: 2B90

Bushing: H 7/8

Belt Size & No.: BX50 X 2

Centerline: 15

I. Fan Capacity Measurements

Test Apparatus: Digital Balometer

Manufacturer: Shortridge

Model: ADM-870

Serial Number: M01465

Cal. Date: 03 Nov 2010

Cal. Due: 02 Nov 2011

SUPPLY FAN TEST DATA

Specified

As Found

Final

Outlet Airflow Total: 4000

5200

4250

Fan Airflow Total: 4000

5360

4300

Fan T.S.P.: 2.2

1.8

1.4

Notes & Observations:



UNIT #
AHU-1

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

II. Measuring Outside Air Volume (SOP: MOSA-0100 TAB)

Test Apparatus: Digital Balometer Accuracy +/-
Manufacturer: Shortridge Model: ADM-870
Serial Number: M01465 Cal. Date: 03 Nov 2010

Direct Measurement: Total CFM: 4300 Return CFM: 300 Outside Air CFM: 1300

Temperature Method: Mixed Air Temp: 71 Return Air Temp: 82 Outside Temp: 45

Calculated Outside Air % = $\frac{\text{RAT-MAT}}{\text{RAT-OAT}} \times 100\% = \frac{82 - 71}{82 - 45} = 30\%$

Calculated Outside Air = 1278.38 CFM +/- 123 CFM Accuracy = +/- 5

Provision for Maintaining Minimum Ventilation Rate: Computer Setting

Normal Setpoint to Maintain Minimum Ventilation Rate: 15%

III. Rotational Speed Measurements (SOP: RM-0100 TAB)

Test Apparatus: Tachometer
Manufacturer: Shimpo Model: DT-205L
Serial Number: COAB0392 Cal. Date: 02 Aug 2010
Cal. Due: 01 Aug 2011

TEST DATA	Specified	Initial	Final
Supply Fan Motor RPM:	1800	1778	1767
Supply Fan RPM:	1000	1200	1089

IV. Electrical Measurements (SOP: EM-0100 TAB)

Test Apparatus: Clamp-On Ammeter
Manufacturer: Fluke Model: 335
Serial Number: 78710854 Cal. Date: 28 Jun 2010
Cal. Due: 27 Jun 2011

TEST DATA	Rating	As Found	Final
Supply Fan Motor Volts:	480	460/457/484	462/577/480
Supply Fan Motor Amp:	33	26/28/22	27/25/23
Supply Fan BHP:	19.2	26.3	25.5
Motor Service Factor:	1.15	Current Overload Rating:	33

Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

V. Static Pressure Measurements (SOP CVSP-0100 TAB)

Test Apparatus: Thermoanemometer / Manometer

Manufacturer: TSI

Model: 8386


Serial Number: 01040114

Cal. Date: 03 Nov 2010

Cal. Due: 02 Nov 2011

TEST DATA	Specified	Initial	Final
Unit E.S.P.:	3.00	2.95	3.25
Supply Fan T.S.P.:	3.50	3.38	3.58

System Diagram



LOCATION	A	B	C	D	E	F	G	H	I	J	K	L	M
As Found	-1.80	-2.23	+1.15										
Final	-1.91	-2.24	+1.34										
100% O/A	-1.99	-2.35	+1.15										
Filter Load	-1.61	-2.45	+1.08										

Notes & Observations:



UNIT #
AHU-1

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

Balancing of Terminal Air Valves (SOP: TAD-0100 TAB)

Air Outlet Terminal				OUTLET						
				Design CFM		Preliminary		Final CFM		
NO.	Area Served	Type	Size	MAX	MIN	Test 1	Test 2	MAX	MIN	%
	Supply Air									
01	Room 101	HEPA	24 x 48	800	400	897	841	810	442	101%
02	Room 102	HEPA	24 x 48	800	300	775	792	808	376	101%
03	Room 103	HEPA	24 x 24	400	200	372	389	398	210	100%
	TOTAL			2000	900	2044		2016	1028	101%



UNIT #
AHU-1

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

Duct Traverse Test Report

System/Unit: AHU-1 / Supply Service: Cleanroom
Location/Zone: Mechanical Room Altitude: 0
Density: 0.075 Corr. Factor: 1.00
Test Apparatus: Thermoanemometer / Manometer Manufacturer: TSI
Model: 8386 Serial: 01040114 Cal. Date/Due: 03 Nov 2010 / 02 Nov 2011

Duct			Design		As Found		Final	
Width	24	in.	SCFM	6200	SCFM	6400	SCFM	6323
Depth	48	in.	CFM	6200	CFM	6400	CFM	6323
Area	8.00	ft ²	FPM	775	FPM	800	FPM	790
Air Temp	70	°F	S.P.	"W.C.	S.P.	2.1 "W.C.	S.P.	2.05 "W.C.

Reading		1	2	3	4	5	6	7	8	9	10	11
Distance from Duct Edge		3	9	15	21							
1	6	700	800	900	800							
2	18	750	850	950	850							
3	30	700	800	900	800							
4	42	650	750	850	750							
5												
6												
7												
8												
9												
10												
11												

Velocity Subtotals	2800	3200	3600	3200								
--------------------	------	------	------	------	--	--	--	--	--	--	--	--

Average Velocity =	12800	(Velocity Total)										
	16	(# of Readings)	=	800	FPM							

Air Volume =	8.00	X	800	=	6400	CFM						
--------------	------	---	-----	---	------	-----	--	--	--	--	--	--

Notes & Observations:



Phone: 888.229.1477
Fax: 888.229.0422



Air Apparatus Report

Project: Sample Balancing Report
Test Performed By: Joe Technician

Report No: None
Report Date: 07 Jan 2011

Unit Data

System/Unit:	FC-3	Model Number:	FC0134
Unit Designation:	FAN COIL UNIT	Serial Number:	123456
Manufacturer:	CARRIER		

Motor Data

Service Factor:	1.0				Nameplate
Motor Manufacturer:	GE		Rated Amps:	4.2	
	Design	Actual	Rated Volts:	208	
HP/Frame:	2	2/218T		L1	L2 L3
RPM:	1600	1550	Operating Amps:	2.7	2.8 2.8
Phase/Hz:	3/60	3/60	Operating Volts:	212	212 212

Fan Data

	Design	Actual		Design	Actual
Supply Air CFM:	1600	1611	Fan Total S.P.(in.):	1.5	1.4
Outside Air CFM:	300	299	External S.P.(in.):	0.75	0.88
Return Air CFM:	1300	1312	Fan RPM:	866	884
Total Outlet Air CFM:	1600	1611	BHP:	1.3	1.6
Provisioning for Maintaining Minimum Ventilation Rate:				DDC CONTROL	
Normal Setpoint to Maintain Minimum Ventilation Rate:				15%	

Other Data

	Actual		Actual
Motor Sheave OD/Bore:	2VP40/H	Fan Sheave OD/Bore:	2B5V50/P1
Motor Sheave Bushing:	H X 7/8	Fan Sheave Bushing:	P1 X 1 5/16
Number of Belts:	2	Sheave Center Dist.:	15"
Belt Size (in.):	BX40	Fan Type:	DWDI-FC

Test Apparatus

Electric Test Apparatus:	Shortridge ADM-870C	Serial Number:	M04816
Rotational Test Apparatus:	Fluke 335	Serial Number:	88105714
Outside Air Test Apparatus:	Shortridge ADM-870C	Serial Number:	M04816

Remarks



UNIT #
FC-4

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report
Test Performed By: Joe Technician
System/Unit: FC-4

Report No: None
Report Date: 07 Jan 2011

Balancing of Terminal Air Valves

Air Outlet Terminal				Outlet		
				Design	Final	
NO.	Area Served	Type	Size	CFM	CFM	%
SUPPLY						
01	Office 100	SD-1	10"	200	215	108%
02	Office 101	SD-1	10"	200	210	105%
03	Office 102	SD-1	10"	200	190	95%
04	Office 103	SD-1	10"	200	180	90%
Totals:				800	795	99%



UNIT #
EF-1

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None


Test Performed By: Jim Clarke

Date: 07 Jan 2011

Duct Traverse Test Report

System/Unit: EF-1 / Exhaust Service: Process Exhaust
Location/Zone: Roof Altitude: 0
Density: 0.075 Corr. Factor: 1.0
Test Apparatus: Thermoanemometer / Manometer Manufacturer: TSI
Model: 8386 Serial: 01040114 Cal. Date/Due: 03 Nov 2010 / 02 Nov 2011

Duct			Design		As Found		Final	
Diameter	14	in.	SCFM	1200	SCFM	0	SCFM	0
			CFM	1200	CFM	0	CFM	0
Area	1.07	ft ²	FPM	1121	FPM	0	FPM	0
Air Temp		°F	S.P.	"W.C.	S.P.	"W.C.	S.P.	"W.C.



Sample Locations	A	B	C	D	E	F	G	H	I	J

Velocity Subtotal 0

Average Velocity 0

Measured Airflow 0

Notes & Observations:



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

Balancing of Terminal Air Valves (SOP: TAD-0506 AEI)

Test Apparatus: Digital Balometer

Manufacturer: Shortridge


Model: ADM-870

Serial Number: M01465

Cal. Date: 03 Nov 2010

Cal. Due: 02 Nov 2011

System Diagram



Notes & Observations:



Phone: 888.229.1477
Fax: 888.229.0422



Fan Report

Project: Sample Balancing Report

Report No: None

Test Performed By: Joe Technician

Report Date: 07 Jan 2011

Unit Data

System/Unit:	EF-2	Model Number:	GB-100
Unit Designation:	Toilet Exhaust	Serial Number:	123456
Manufacturer:	Greenheck		

Motor Data

Service Factor:	1.15	Nameplate			
Motor Manufacturer:	Marathon	Rated Amps:	5.0		
	<u>Design</u>	<u>Actual</u>	Rated Volts:	208	
HP/Frame:	1	0.75/48Y		<u>L1</u>	<u>L2</u>
RPM:	1725	1770	Operating Amps:	4.1	4.2
Phase/Hz:	3/60	3/60	Operating Volts:	212	213
					214

Fan Data

	<u>Design</u>	<u>Actual</u>		<u>Design</u>	<u>Actual</u>
Fan Air CFM:	2000	1975	Fan Total S.P.(in.):	0.5	0.45
Total Outlet CFM:	2100	1888	External S.P.(in.):	0.3	0.32
Fan Rpm:	1000	1050			

Other Data

	<u>Actual</u>		<u>Actual</u>
Motor Sheave OD/Bore:	1VL34/1/2	Fan Sheave OD/Bore:	AK60/1"
Motor Sheave Bushing:	NA	Fan Sheave Bushing:	NA
Number of Belts:	1	Sheave Center Dist.:	8"
Belt Size (in.):	AX22	Type of Service:	GENERAL EXHAUST
Unit Type/Size/Arrangement/Class: DWDI-BI / 10" / UPBLAST / II			

Test Apparatus

Electric Test Apparatus:	Fluke 335	Serial Number:	78710854
Rotational Test Apparatus:	Shimpo DT-205L	Serial Number:	COAB0392
Airflow Test Apparatus:	Shortridge ADM-870	Serial Number:	M01465

Remarks



UNIT #
VAV-1

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

Balancing of Terminal Air Devices (SOP: TAD-0100 TAB)

Test Apparatus: Digital Balometer

Manufacturer: Shortridge


Model: ADM-870

Serial Number: M01465

Cal. Date: 03 Nov 2010

Cal. Due: 02 Nov 2011

System Diagram



Air Outlet Terminal				OUTLET		
				Design	Final	
NO.	Area Served	Type	Size	CFM	CFM	%
Supply						
01	Room A	CD	24 x 24	300	305	102%
02	Room B	CD	24 x 24	280	288	103%
03	Room C	CD	24 x 24	320	319	100%
	TOTAL			900	912	101%



UNIT #
EF-1

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

Constant Volume Exhaust System

Unit Number: EF-1

Location: Roof Service: Process Room

Manufacturer: Exhaust Fan Company

Model: Exhaust-matic

Serial: 5551212

Filtration: Bag-in Bag-out HEPA & Charcoal

Heat Recovery: None

Exhaust Fan Data

Fan Type: DWDI-FC

Fan Size: 16

Manufacturers; Fan: Exhausto

Motor: Electro

Specified Motor HP: 10

Nameplate: 10

Specified Motor RPM: 1800

Nameplate: 1750

Specified Motor Volts: 200

Nameplate: 208

Motor Sheave Size: 1VP60

Bushing: None Required

Fan Sheave Size: BK160

Bushing: P1 x 1 1/16

Belt Size & No.:

Centerline:

I. Fan Capacity Measurements

Test Apparatus: Digital Balometer

Manufacturer: Shortridge

Model: ADM-870

Serial Number: M01465

Cal. Date: 03 Nov 2010

Cal. Due: 02 Nov 2011

FAN TEST DATA	Specified	As Found	Final
Outlet Airflow Total:	2000	1600	1975
Fan Airflow Total:	2000	1875	1950
Fan T.S.P.:	2.2	2.8	2.4

Notes & Observations:



UNIT #
EF-1

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

II. Rotational Speed Measurements (SOP: RM-0100 TAB)

Test Apparatus: Tachometer
Manufacturer: Shimpco Model: DT-205L
Serial Number: COAB0392 Cal. Date: 02 Aug 2010
Cal. Due: 01 Aug 2011

TEST DATA	Specified	As Found	Final
Exhaust Fan Motor RPM:	1800	1778	1766
Exhaust Fan RPM:	654	621	708

III. Electrical Measurements (SOP: EM-0100 TAB)

Test Apparatus: Clamp-On Ammeter
Manufacturer: Fluke Model: 335
Serial Number: 78710854 Cal. Date: 28 Jun 2010
Cal. Due: 27 Jun 2011

TEST DATA	Rating	As Found	Final
Exhaust Fan Motor Volts:	200	229/218/220	212/214/215
Exhaust Fan Motor Amp:	7.8	5.4	6.7
Exhaust Fan BHP:	7.7	6.9	8.1

Motor Service Factor: 1.16 Current Overload Rating: 7.8

Notes & Observations:



UNIT #
EF-2

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None

Test Performed By: Joe Technician

Date: 07 Jan 2011

Fume Hood Face Velocity Report

System/Unit: EF-2

Fume Hood #: FH-15

Room #: C1015

Serial Number:

Sash Opening	Horizontal	Vert Max	Vert Min
Height (inches)	14		
Width (inches)	48		
Area (square feet)	4.67	NA	NA
Average Face Velocity (FPM)	100.00	100.00	100.00
Exhaust Airflow (CFM)	466.67	NA	NA

Horizontal Sash Opening

Face Velocity FPM								
No.	1	2	3	4	5	6	7	8
1	101.0	110.0	99.0	95.0	100.0	NA	NA	NA
2	110.0	105.0	102.0	110.0	90.0	NA	NA	NA
3	102.0	99.0	95.0	92.0	90.0	NA	NA	NA

Vertical Sash Maximum Opening

Face Velocity FPM								
No.	1	2	3	4	5	6	7	8
1	105.0	95.0	100.0	105.0	95.0	NA	NA	NA
2	95.0	105.0	105.0	100.0	95.0	NA	NA	NA
3	105.0	100.0	95.0	95.0	105.0	NA	NA	NA

Vertical Sash Minimum Opening

Face Velocity FPM								
No.	1	2	3	4	5	6	7	8
1	105.0	100.0	95.0	101.0	99.0	NA	NA	NA

Notes & Observations:



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

Room Pressure Differentials (SOP: TAD-0100 TAB)

Test Apparatus: Digital Balometer

Manufacturer: Alnor


Model: EBT721

Serial Number: 90826015


Cal. Date: 02 Jun 2010

Cal. Due: 01 Jun 2011

System Diagram



Notes & Observations:





UNIT #
CC-1

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

Chilled Water Cooling Coil

Test Apparatus: Hydronic Multimeter

Manufacturer: Shortridge

Model: HDM-300

Serial Number: W05025

Cal. Date: 02 Aug 2010

Test Apparatus: Thermoanemometer / Manometer

Manufacturer: TSI

Model: 8386

Serial Number: 01040114

Cal. Date: 03 Nov 2010

Design

Coil Location
Area Served
Coil Manufacturer
Capacity
Coil Face Size
Coil Face Velocity
Airflow Rate, CFM
Air Pressure Drop "W.C.

Air Handling Unit 1
Cleanroom
Quick Coil
3600 MBH
42" x 50"
550
2000
0.5" W.C.

Actual

Duct mounted
Cleanroom
Cold Coil
3800 MBH
48" x 48"
565
2200
0.65 " W.C.

Water Flow, GPM
Balancing Valve Size
Valve Type & Position
Valve Pressure Drop
Coil Pressure Drop, ft.

35
2"
CBV
15 Feet
2.3 ft

33
2"
CBV
15 Feet
3.1 Ft

Entering Air Temp D.B.
Entering Air Temp W.B.
Leaving Air Temp D.B.
Leaving Air Temp W.B.
Entering Water Temp
Leaving Water Temp

93
86
55
53
42
56

98
78
58
57
44
57

Relative Humidity of Entering Air

45%

Relative Humidity of Leaving Air

98%

Calculated Latent Heat Transferred From Air

1900

BTUH

Calculated Sensible Heat Transferred From Air

1500

BTUH

Calculated Total Heat Transferred From Air

3400

BTUH

Calculated Heat Quantity Transferred to Water

3650

BTUH

Heat Loss 250

BTUH

Calculated Water Flow

37

GPM

Notes & Observations:



Coil Apparatus Report

Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

System/Unit: COOLING COIL CC-1

1. Unit Data

Unit Identification:	AHU-1	Location:	PENTHOUSE	Model #:	CC-205
Manufacturer:	TRANE	Type:	TSW	Size:	440
Unit Arrangement:	DRAW THROUGH	Disch. Arr:	VERTICAL	Class:	II
				Filters:	95%

2. Motor Data

Manufacturer: BALDOR Frame: 215T HP: 5 V/Ph/Hz: 208 / 3 / 60 FLA: 7.2 S.F.: 1.15

3. Coil Data

System ID:	COOLING COIL #1	Location:	AHU-1	Type:	CHILLED WATER
Manufacturer:	TRANE	Model #:	TSW140DEF0004	Face Area:	20" X 80"
Fins Spacing:	10/IN	Fin Material:	ALUMINUM	Circuit Arr.:	SERPENTINE
Tube Size:	1/2"	Tube Material:	COPPER	# of Rows:	4

4. Test Data

	Design	Actual		Design	Actual	Notes
Total Airflow (cfm):	4000	4100	System S.P. ("wc):	2"	2.15"	
Filter Press. ("wc):	0.3"	0.33"	Discharge S.P. ("wc):	1"	1.15"	
Cool Airflow (cfm):	4000	4100	Coil P.D. ("wc):	0.5"	0.62"	
Fan RPM:	750	737	Coil Face Velocity(fpm):	440	451	
Outside Airflow:	1000	1010	O.A. Temp DB (°F):	55	61	
OAD Position (%):	10%	15%	O.A. Temp WB (°F):	51	57	
Return Airflow:	3000	3090	R.A. Temp DB (°F):	77	74	
RAD Position (%):	90%	85%	R.A. Temp WB (°F):	60	64	
Water Flow (gpm):	75	77	E.A. Temp DB (°F):	71	70	
Water DP (ft. hd.):	10 FT (max)	9.2	E.A. Temp WB (°F):	53	62	
E.W. Temp (°F):	44	42.5	L.A. Temp DB (°F):	55	53	
L.W. Temp (°F):	55	53.3	L.A. Temp WB (°F):	54	52	

5. Test Apparatus

Rotational Test Apparatus:	Shimpo DT-205L	Serial #:	COAB0392
Airflow Test Apparatus:	Alnor EBT721	Serial #:	90835040
Pressure Test Apparatus:	Fluke 922	Serial #:	96700033
Water Flow Test Apparatus:	Alnor HM670	Serial #:	70931051
Temperature Test Apparatus:	Cooper Instrument SRH77A	Serial #:	483656

6. Remarks



UNIT #
CHP-1

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

Hydronic Circulating Pump

Test Apparatus: Hydronic Multimeter

Manufacturer: Shortridge

Model: HDM-300

Serial Number: W05025

Cal. Date: 02 Aug 2010

Unit Number: CHP-1

Location: Pump Room

Service: Chilled Water

Manufacturer / Model: Pump-It Company / 555-ghp

Serial: 246897531

Pump Data

	Design	Actual
Pump Type	End Suction	Inline
Mounting Arrangement	Base Mounted	Pipe-Hung
Inlet Size	3"	3"
Discharge Size	2 1/2"	2"
Coupling Type	Flexible	Direct
Seal Type	Graphite	Metallic
Body Material	Brass	Cast Iron
Impeller Material	Stainless	Bronze
Net Positive Suction Head	14	12
Motor Manufacturer	Electric & Electric	Electric Co
Motor HP/Frame	15/254T	10/182T
Motor RPM	1800	1140
Motor Voltage	200	208
Nameplate Amperage	12.5	Measured Currents 10.8 / 11.0 / 11.2
Service Factor	1.15	Current Overload Protection 12.5 A

Test Data

Measured Head Pressures	No Flow or Dead Head			Normal Operation - Full Flow	
	50			38	
	10			19	
	40.00			19.00	
	92.40			43.89	
Pump Performance	Design	Pump Body	Submittal	Calculated	Measured
Impeller Size	7.75	7.5	7.5	8.0	Not Measured
Flow Rate	300	325	325	315	335
Head Pressure	45 ft	50 ft	50 ft	48	48.5
Notes & Observations:					



Phone: 888.229.1477
Fax: 888.229.0422



Balancing Valve/Flow Meter Report

Project: Sample Balancing Report
Test Performed By:
System/Unit: Hot Water Coils

Report No: None
Report Date: 07 Jan 2011

Balancing Valve/Flow Meter Report

Test Apparatus: Hydronic Multimeter

Serial Number: W03013

No.	Service Designation	Manufacturer	Model	Size	Design Flow	Actual Flow	Dial Set	Delta P	Op. Pres. Range
Sub-System									
01									
02									
03									
04									
05									
06									
07									
08									
09									
10									
11									
12									
13									
14									
15									
16									
19									
20									
				TOTAL					



UNIT #
Hot Water Heating

Phone: 888.229.1477
Fax: 888.229.0422



Project: Sample Balancing Report

Report No: None

Test Performed By: Jim Clarke

Date: 07 Jan 2011

Balancing Valve/Flow Meter Report

Test Apparatus: Hydronic Multimeter

Manufacturer: Shortridge

Model: HDM-300

Serial Number: W05025

Cal. Date: 02 Aug 2010

Cal. Due: 01 Aug 2011

Service or Designation	Manufacturer	Model	Size	Design GPM	Valve Position	Valve P.D.	Actual GPM	Notes
2nd Floor								
HC-1	Coilco	BFG10	1"	10	50%	15 ft	11	
HC-2	Coilco	BFG15	1.5"	15	40%	25 ft	14	
HC-3	Coilco	BFG20	2.0"	25	100%	1 ft	23	
	TOTAL			50.0			48.0	



microcln.com

Micro-Clean, Inc.
P.O. Box 21806
Lehigh Valley, PA 18002-1806610-867-5302
1-800-523-9852
Fax: 610-954-7803

CERTIFICATE OF CALIBRATION

MODEL 8386 SERIAL NO. 01040114
DESCRIPTION TSI VelociCalc Plus Thermoanemometer

Micro-Clean Calibration Services does hereby certify that all performance and acceptance tests required were successfully conducted according to required specifications. All calibration data and test instrumentation used have been obtained using standards whose accuracies are traceable to the National Institute of Standards and Technology (NIST), have been derived from accepted values of natural physical constants, or by the use of ratio type of self calibration. The calibration system complies with ANSI/NCSL Z540-1-1994.

November 3, 2010
Date of Calibration

November 2, 2011
Next Calibration is Due

Ed Pitosky Ed Pitosky 03 NOV 2010
Authorized Name/Signature/Date

MCI# 105087



MICRO-CLEAN CALIBRATION SERVICES
177 North Commerce Way
Bethlehem, PA 18017-8933
(800) 523-9852

Page 1 of 1

CALIBRATION CERTIFICATE

Manufacturer: TSI
Model: 8386
Serial Number: 01040114
Description: VelociCalc Plus
Noun: Thermoanemometer
MCI #: 105087

Customer: AEI AIRFLOW EXPERTS INC.
Address: PO BOX 418
GRAM, NC 27253

Last Calibration Date: October 7, 2009
Calibration Date: November 3, 2010
Calibration Due: November 2, 2011

Ambient Temperature: 69 °F
Relative Humidity: 25 % RH
Barometric Pressure: 29.90 in.Hg

Calibrated by: Ed Pitosky *Ed Pitosky* 03 NOV 2010

MCI Quality Assurance approval: *Thomas A. Zeleny* 05 NOV 2010

All results contained within this certification relate only to item(s) calibrated.

This certificate shall not be reproduced except in full, without the written consent of Micro-Clean Calibration Services.
Micro-Clean Calibration Services quality system complies with applicable requirements of ANSI/NCCL Z540-1-1994.

NOMINAL	AS FOUND	AS LEFT	Test accuracy ratio	TOLERANCE (ft / min)	
50 ft / min	50 ft / min	50 ft / min	1.0 : 1	47	53
100 ft / min	100 ft / min	100 ft / min	< 1.0 : 1	97	103
200 ft / min	202 ft / min	202 ft / min	1.0 : 1	194	206
500 ft / min	510 ft / min	510 ft / min	1.0 : 1	485	515
1000 ft / min	1005 ft / min	1005 ft / min	1.2 : 1	970	1030
2000 ft / min	1980 ft / min	1980 ft / min	1.7 : 1	1940	2060
3500 ft / min	3470 ft / min	3470 ft / min	2.1 : 1	3395	3605
6000 ft / min	5890 ft / min	5890 ft / min	2.8 : 1	5820	6180
9000 ft / min	9250 ft / min	9250 ft / min	2.6 : 1	8730	9270

FUNCTION: Velocity

TOLERANCE: $\pm 3.0\%$ of reading or ± 3 ft / min, whichever is greater

SOP NUMBER: TA-1108 CAL

NOMINAL	AS FOUND	AS LEFT	Test accuracy ratio	TOLERANCE (in. W.C.)	
-4.00 in. W.C.	-4.010 in. W.C.	-4.010 in. W.C.	3.0 : 1	-4.045	-3.955
-2.50 in. W.C.	-2.500 in. W.C.	-2.500 in. W.C.	1.7 : 1	-2.530	-2.470
0.000 in. W.C.	0.000 in. W.C.	0.000 in. W.C.	NA	-0.005	0.005
0.050 in. W.C.	0.050 in. W.C.	0.050 in. W.C.	< 1.0 : 1	0.045	0.056
0.100 in. W.C.	0.100 in. W.C.	0.100 in. W.C.	< 1.0 : 1	0.094	0.106
0.500 in. W.C.	0.501 in. W.C.	0.501 in. W.C.	< 1.0 : 1	0.490	0.510
1.000 in. W.C.	1.002 in. W.C.	1.002 in. W.C.	1.0 : 1	0.985	1.015
2.000 in. W.C.	2.005 in. W.C.	2.005 in. W.C.	1.7 : 1	1.975	2.025
4.000 in. W.C.	4.010 in. W.C.	4.010 in. W.C.	3.0 : 1	3.955	4.045
9.000 in. W.C.	9.025 in. W.C.	9.025 in. W.C.	> 4.0 : 1	8.905	9.095
12.00 in. W.C.	12.040 in. W.C.	12.040 in. W.C.	> 4.0 : 1	11.875	12.125

FUNCTION: Pressure

TOLERANCE: $\pm 1.0\%$ of reading, ± 0.005 in. W.C.

SOP NUMBER: PRSS-0709 CAL

NOMINAL	AS FOUND	AS LEFT	Test accuracy ratio	TOLERANCE (°F)	
69.318 °F	69.4 °F	69.4 °F	10:1	68.8	69.8

FUNCTION: Temperature

TOLERANCE: $\pm 0.5^\circ$ Fahrenheit

SOP NUMBER: TEMP-1208 CAL

NOMINAL	AS FOUND	AS LEFT	Test accuracy ratio	TOLERANCE (%RH)	
LiCl (12.4 %)	0.0 % RH	0.0 % RH	NA	9.4	15.4
K ₂ CO ₃ (44.0 %)	0.0 % RH	0.0 % RH	NA	41.0	47.0
NaCl (75.5 %)	0.0 % RH	0.0 % RH	NA	72.5	78.5

FUNCTION: Humidity

TOLERANCE: $\pm 3.0\%$ Relative Humidity

SOP NUMBER: TEMP-1208 CAL

Comments: Unit received in tolerance, unit returned in tolerance, (limited calibration not to be used for humidity).

NOTE 1: Velocity Corrected for Std. Conditions

NOTE 2: * Asterisk indicates out-of-tolerance condition

CALIBRATION STANDARDS

Description	Part Number	Serial Number	Calibration Date	Date Due
Wind Tunnel Transducer	MKS 225AD	14935015/00334	May 17, 2010	May 16, 2011
Temperature IRTD	Kaye M2801	90414	October 1, 2010	September 30, 2011
Pressure Standard	Heise ST-2H	50560	September 8, 2010	September 8, 2011
Pressure Standard	Heise HQS-1	19205	January 28, 2010	January 27, 2011
RH Reference	LiCl (12.4%) RH	NA	NA	NA
RH Reference	K ₂ CO ₃ (44.0%) RH	NA	NA	NA
RH Reference	NaCl (75.5%) RH	NA	NA	NA

553-E Pylon Drive • Raleigh, NC 27607
(919) 755-0382
FAX 755-0383**ISO/IEC 17025
Accredited****CALIBRATION CERTIFICATE**

INSTRUMENT: Alnor - HM 670

SERIAL NO.: 70931051

DESCRIPTION: Hydronic Manometer

PROPERTY OF: Airflow Experts Inc.

TEST PERFORMED BY: R.Hammerle

TEST DATE: 08/27/10

TEMPERATURE: 23°C HUMIDITY: 45%

NEXT CALIBRATION DUE: 08/27/2011

CERTIFICATE NO.: 100827-7

The above instrument was checked and calibrated against working standards which are traceable to the National Institute of Standards Technology. The metrology procedures utilized conform to and satisfy the requirements of ISO/IEC 17025: 2005, ISO 10012-1, and ANSI/NCSL Z540.3-2006. The above instrument performance was determined using the specifications available from the manufacturer or some equivalent acceptable reference or PMC procedures specified in the QA manual. Expanded uncertainties represent uncertainties expressed at the 95% confidence level using a coverage factor of K=2. Although the item calibrated meets the specifications and performance at the time of calibration, due to any number of factors, the recommended due date of the item calibrated does not imply continuing conformance to specifications during the recommended interval. This certificate shall not be reproduced, except in full, without prior written approval of the laboratory.

Instrument Received: Within Tolerance

Instrument Returned: Within Tolerance



Authorized Signature



**ISO/IEC 17025
Accredited**

553-E Pylon Drive • Raleigh, NC 27607
(919) 755-0382
FAX 755-0383

TEST REPORT

Company:	Airflow Experts Inc.
Certificate No.:	1008277
Manufacturer:	Alnor
Model:	HM 670
Serial No:	70931051
Test Date:	08/27/10
Temperature:	23 °C
Relative Humidity:	45%
Description:	Hydronic Manometer
Accuracy:	+/-1% of reading or .036psi whichever is greater
Repair Status:	N/A
Calibration Specs:	Manufacturer

Calibration Data

	Standard	Before	After		Standard	Before	After
1	High PSI 5.000	5.002	Same As Received	7	Low PSI 5.000	5.002	SAR
2	50.00	50.03	SAR	8	50.00	50.01	SAR
3	100.00	100.1	SAR	9	100.00	99.9	SAR
4	150.00	150.1	SAR	10	150.00	149.8	SAR
5	200.00	200.2	SAR	11	200.00	199.7	SAR
6	300.00	300.3	SAR	12	300.00	299.6	SAR

Standards Used

Manufacturer	Model	Serial No.	Date Cal.	Due Cal.	Description	Best Uncertainty
Beta	320	12139	02/12/10	2/2011	Precision Pressure Calibrator	0-30psi +/- .001psi 0-300psi +/- .01psi 0-3000psi +/- .5psi 0-30"Hg +/- .01"Hg

Applicable NIST Tests

Pressure- 821/248681; 821/229629; 821/316451; 737/236653; 52/-236653; QSP-A012; MMAF822/LA



553-E Pylon Drive • Raleigh, NC 27607
(919) 755-0382
FAX 755-0383

ISO/IEC 17025
Accredited

CALIBRATION CERTIFICATE

INSTRUMENT: Alnor - EBT-721 / 800188 / 800189

SERIAL NO.: 90826015 / 90824074 / 90825020

DESCRIPTION: Balometer / Temp Probe / Humidity Probe

PROPERTY OF: Airflow Experts Inc.

TEST PERFORMED BY: B.Cullen

TEST DATE: 06/02/10

TEMPERATURE: 23°C HUMIDITY: 45%


NEXT CALIBRATION DUE: 06/02/2011

CERTIFICATE NO.: 100602-3

The above instrument was checked and calibrated against working standards which are traceable to the National Institute of Standards Technology. The metrology procedures utilized conform to and satisfy the requirements of ISO/IEC 17025, ISO 10012-1, and ANSI/NCSL Z540-3-1994. The above instrument performance was determined using the specifications available from the manufacturer or some equivalent acceptable reference or PMC procedures specified in the QA manual. Expanded uncertainties represent uncertainties expressed at the 95% confidence level using a coverage factor of K=2. Although the item calibrated meets the specifications and performance at the time of calibration, due to any number of factors, the recommended due date of the item calibrated does not imply continuing conformance to specifications during the recommended interval. This certificate shall not be reproduced, except in full, without prior written approval of the laboratory.

Instrument Received: Within Tolerance

Instrument Returned: Within Tolerance



Authorized Signature



**ISO/IEC 17025
Accredited**

553-E Pylon Drive • Raleigh, NC 27607
(919) 755-0382
FAX 755-0383

TEST REPORT

Company:	Airflow Experts Inc.
Certificate No.:	1006023
Manufacturer:	Alnor
Model:	EBT-721 / 800188 / 800189
Serial No:	90826015 / 90824074 / 90825020
Test Date:	06/02/10
Temperature:	23 °C
Relative Humidity:	45%
Description:	Balometer / Temp Probe / Humidity Probe
Accuracy:	Airflow+/-3% Full Scale +/-5 Deg F RH+/-3%
Repair Status:	N/A
Calibration Specs:	Manufacturer

Standards Used

Manufacturer	Model	Serial No.	Date Cal.	Due Cal.	Description	Best Uncertainty
Alphagaz	Calgaz	90-1086	10/08/07	10/2010	Nitrogen	99.995 to 99.999
Beta	320	12139	02/12/10	2/2011	Precision Pressure Calibrator	0-30psi +/-0.01psi 0-300psi +/-0.1psi 0-3000psi +/-0.5psi 0-30"Hg +/-0.1"Hg
Fisher Scientific	14-649-6	20234990	06/02/09	6/2012	Precision Stop Watch	+/-0.0003%
Omega	CL-505A	91064671	10/30/09	10/2010	Precision Temperature Calibrator	+/-1 Deg C +/-2 Deg F mV +/-0.05% mA +/-0.05%
Reagents inc.	11.3% to 97.3%	PMC-16	05/04/09	5/2011	Saturated Aqueous Salt Solutions	+/-1%
Oakton	35612-00	9009291	01/04/10	1/2011	Thermohygrometer	+/-2% RH +/-6 Deg C

Applicable NIST Tests

DC Voltage- 811/249920-92; 243290; 2300010062; 2300010061, Frequency- WWVB; 2300009707, Humidity- Saturated Salt Solutions, Pressure- 821/248681; 821/229629; 821/316451; 737/236653; 52/236653; QSP-A012; MMAP822/LA, Temperature- 238455; 130734; 37488-40832



Airflow Experts Inc.

TEST REPORT

Certificate No: 1006023

Calibration Data

	Standard	Before	After		Standard	Before	After
1	FPM 24	25	Same As Received	26			
2	197	200	SAR	27			
3	296	300	SAR	28			
4	395	400	SAR	29			
5	494	500	SAR	30			
6	795	800	SAR	31			
7	1206	1200	SAR	32			
8	1607	1600	SAR	33			
9	2011	2000	SAR	34			
10	2532	2500	SAR	35			
11	Deg F 32.0	32.2	SAR	36			
12	50.0	50.2	SAR	37			
13	75.0	75.3	SAR	38			
14	100.0	100.3	SAR	39			
15	150.0	150.3	SAR	40			
16	200.0	200.3	SAR	41			
17	250.0	249.7	SAR	42			
18	%RH 22.0	22.3	SAR	43			
19	43.0	43.4	SAR	44			
20	75.0	75.5	SAR	45			
21	90.0	90.6	SAR	46			
22				47			
23				48			
24				49			
25				50			



CERTIFICATE OF CALIBRATION

TSI Incorporated, Alnor Products, 500 Cardigan Road, Shoreview, MN 55126 USA
TEL: 1-800-874-2811 1-651-490-2811 FAX: 1-651-490-3824 www.alnor.com

ENVIRONMENT CONDITION		
TEMPERATURE	71.1	° F
RELATIVE HUMIDITY	30.0	% RH
BAROMETRIC PRESSURE	29.24	inHg

MODEL	EBT™ Micromanometer EBT721
SERIAL NO.	90835040

CALIBRATION STANDARDS USED	
Manometer Calibration Bench 1	

<input checked="" type="checkbox"/> AS LEFT	<input checked="" type="checkbox"/> IN TOLERANCE
<input type="checkbox"/> AS FOUND	<input type="checkbox"/> OUT OF TOLERANCE

CALIBRATION DATA						
TESTING POINTS	BAROMETRIC PRESSURE MEASURED IN in.Hg			DIFFERENTIAL PRESSURE MEASURED IN in.H ₂ O		
	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE
1	20.06	20.04	19.66 ~ 20.46	0.097	0.097	0.095 ~ 0.099
2	29.20	29.20	28.62 ~ 29.78	0.483	0.483	0.473 ~ 0.493
3	34.47	34.46	33.79 ~ 35.15	2.85	2.85	2.80 ~ 2.90
4	-	-	-	12.0	12.0	11.8 ~ 12.2
5	-	-	-	15.1	15.1	14.8 ~ 15.4

TESTING POINTS	TEMPERATURE MEASURED IN °F			HUMIDITY MEASURED IN %RH		
	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE
1	-38.0	-38.0	-37.0 ~ -39.0	71.4	71.5	71.3 ~ 71.5
2	5.0	5.0	4.7 ~ 5.3	5.6	5.6	5.5 ~ 5.7
3	77.0	77.0	76.8 ~ 77.2	-	-	-
4	158.0	158.0	157.8 ~ 158.2	-	-	-
5	230.0	230.0	229.7 ~ 230.3	-	-	-

* Indicates out of tolerance condition

TSI Incorporated does hereby certify that the above described instrument conforms to the original manufacturer's specifications (not applicable to As Found data) and has been calibrated using standards whose accuracies are traceable to the National Institute of Standards and Technology within the limitations of NIST's calibration services or have been derived from accepted values of natural physical constants or have been derived by the ratio type of self calibration techniques. The calibration ratio for this instrument is at least 6.7:1 for barometric pressure and 3:1 for differential pressure. TSI's calibration system meets ISO-9001:2008 and complies with ISO 10012:2003, Quality Assurance Requirements for Measuring Equipment. This report may not be reproduced, except in full, unless permission for the publication of an approved abstract is obtained in writing from the calibration organization issuing this report.

Measurement Variable	System ID Number	Date Last Calibrated	Calibration Due Date
DC Voltage	E002798	06-24-10	12-24-11
DC Voltage	E002797	06-24-10	12-24-11
Pressure	E002173	06-16-10	12-16-10
Pressure	E002447	06-30-10	06-30-11

Calibration procedure used: 10000000787B

Thay Xiong
Calibrated By

Nov. 2, 2010

Calibration Date



CERTIFICATE OF CALIBRATION

TSI Incorporated, Alnor Products, 500 Cardigan Road, Shoreview, MN 55126 USA
TEL: 1-800-874-2811 1-651-490-2811 FAX: 1-651-490-3824 www.alnor.com

ENVIRONMENT CONDITION		
TEMPERATURE	21.7	°C
RELATIVE HUMIDITY	30.0	% RH
BAROMETRIC PRESSURE	990	hPa

MODEL	EBT™ Micromanometer EBT721
SERIAL NO.	90835040

CALIBRATION STANDARDS USED	
Manometer Calibration Bench 1	

<input checked="" type="checkbox"/> AS LEFT	<input checked="" type="checkbox"/> IN TOLERANCE
<input type="checkbox"/> AS FOUND	<input type="checkbox"/> OUT OF TOLERANCE

CALIBRATION DATA						
TESTING POINTS	BAROMETRIC PRESSURE MEASURED IN hPa			DIFFERENTIAL PRESSURE MEASURED IN Pa		
	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE
1	679	679	665 ~ 693	24.2	24.2	23.5 ~ 24.9
2	989	989	969 ~ 1009	120	120	117 ~ 123
3	1167	1167	1144 ~ 1190	710	710	696 ~ 724
4	-	-	-	2989	2989	2929 ~ 3049
5	-	-	-	3761	3761	3686 ~ 3836

TESTING POINTS	TEMPERATURE MEASURED IN °C			HUMIDITY MEASURED IN %RH		
	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE
1	-38.9	-38.9	-38.3 ~ -39.4	71.4	71.5	71.3 ~ 71.5
2	-15.0	-15.0	-14.8 ~ -15.2	5.6	5.6	5.5 ~ 5.7
3	25.0	25.0	24.9 ~ 25.1	-	-	-
4	70.0	70.0	69.9 ~ 70.1	-	-	-
5	110.0	110.0	109.8 ~ 110.2	-	-	-

* Indicates out of tolerance condition

TSI Incorporated does hereby certify that the above described instrument conforms to the original manufacturer's specifications (not applicable to As Found data) and has been calibrated using standards whose accuracies are traceable to the National Institute of Standards and Technology within the limitations of NIST's calibration services or have been derived from accepted values of natural physical constants or have been derived by the ratio type of self calibration techniques. The calibration ratio for this instrument is at least 6.7:1 for barometric pressure and 3:1 for differential pressure. TSI's calibration system meets ISO-9001:2008 and complies with ISO 10012:2003, Quality Assurance Requirements for Measuring Equipment. This report may not be reproduced, except in full, unless permission for the publication of an approved abstract is obtained in writing from the calibration organization issuing this report.

Measurement Variable	System ID Number	Date Last Calibrated	Calibration Due Date
DC Voltage	E002798	06-24-10	12-24-11
DC Voltage	E002797	06-24-10	12-24-11
Pressure	E002173	06-16-10	12-16-10
Pressure	E002447	06-30-10	06-30-11

Calibration procedure used: 10000000787B

Thay Xiong
Calibrated By

Nov. 2, 2010

Calibration Date



CERTIFICATE OF CALIBRATION

TSI Incorporated, Alnor Products, 500 Cardigan Road, Shoreview, MN 55126 USA
TEL: 1-800-874-2811 1-651-490-2811 FAX: 1-651-490-3824 www.alnor.com

ENVIRONMENT CONDITION		
TEMPERATURE	71.1	° F
RELATIVE HUMIDITY	30.0	% RH
BAROMETRIC PRESSURE	29.24	inHg

MODEL	EBT™ Micromanometer EBT721
SERIAL NO.	90835040

CALIBRATION STANDARDS USED	
Manometer Calibration Bench 1	

<input type="checkbox"/> AS LEFT	<input checked="" type="checkbox"/> IN TOLERANCE
<input checked="" type="checkbox"/> AS FOUND	<input type="checkbox"/> OUT OF TOLERANCE

CALIBRATION DATA						
TESTING POINTS	BAROMETRIC PRESSURE MEASURED IN in.Hg			DIFFERENTIAL PRESSURE MEASURED IN in.H ₂ O		
	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE
1	20.06	19.87	19.66 ~ 20.46	0.093	0.094	0.091 ~ 0.095
2	29.21	29.02	28.63 ~ 29.79	0.480	0.484	0.470 ~ 0.490
3	34.47	34.25	33.79 ~ 35.15	2.83	2.85	2.78 ~ 2.88
4	-	-	-	11.9	12.0	11.7 ~ 12.1
5	-	-	-	15.1	15.3	14.8 ~ 15.4

TESTING POINTS	TEMPERATURE MEASURED IN °F			HUMIDITY MEASURED IN %RH		
	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE
1	-38.0	-38.0	-37.0 ~ -39.0	71.4	71.5	71.3 ~ 71.5
2	5.0	5.0	4.7 ~ 5.3	5.6	5.6	5.5 ~ 5.7
3	77.0	77.0	76.8 ~ 77.2	-	-	-
4	158.0	158.0	157.8 ~ 158.2	-	-	-
5	230.0	230.0	229.7 ~ 230.3	-	-	-

* Indicates out of tolerance condition

TSI Incorporated does hereby certify that the above described instrument conforms to the original manufacturer's specifications (not applicable to As Found data) and has been calibrated using standards whose accuracies are traceable to the National Institute of Standards and Technology within the limitations of NIST's calibration services or have been derived from accepted values of natural physical constants or have been derived by the ratio type of self calibration techniques. The calibration ratio for this instrument is at least 6.7:1 for barometric pressure and 3:1 for differential pressure. TSI's calibration system meets ISO-9001:2008 and complies with ISO 10012:2003, Quality Assurance Requirements for Measuring Equipment. This report may not be reproduced, except in full, unless permission for the publication of an approved abstract is obtained in writing from the calibration organization issuing this report.

Measurement Variable	System ID Number	Date Last Calibrated	Calibration Due Date
DC Voltage	E002798	06-24-10	12-24-11
DC Voltage	E002797	06-24-10	12-24-11
Pressure	E002173	06-16-10	12-16-10
Pressure	E002447	06-30-10	06-30-11

Calibration procedure used: 10000000787B

T. Hung Xiong
Calibrated By

Nov. 2, 2010

Calibration Date



CERTIFICATE OF CALIBRATION

TSI Incorporated, Alnor Products, 500 Cardigan Road, Shoreview, MN 55126 USA
TEL: 1-800-874-2811 1-651-490-2811 FAX: 1-651-490-3824 www.alnor.com

ENVIRONMENT CONDITION		
TEMPERATURE	21.7	°C
RELATIVE HUMIDITY	30.0	% RH
BAROMETRIC PRESSURE	990	hPa

MODEL	EBT™ Micromanometer EBT721
SERIAL NO.	90835040

CALIBRATION STANDARDS USED	
Manometer Calibration Bench 1	

<input type="checkbox"/> AS LEFT	<input checked="" type="checkbox"/> IN TOLERANCE
<input checked="" type="checkbox"/> AS FOUND	<input type="checkbox"/> OUT OF TOLERANCE

CALIBRATION DATA						
TESTING POINTS	BAROMETRIC PRESSURE MEASURED IN hPa			DIFFERENTIAL PRESSURE MEASURED IN Pa		
	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE
1	679	673	665 ~ 693	23.2	23.4	22.5 ~ 23.9
2	989	983	969 ~ 1009	120	121	117 ~ 123
3	1167	1160	1144 ~ 1190	705	710	691 ~ 719
4	-	-	-	2964	2989	2905 ~ 3024
5	-	-	-	3761	3811	3686 ~ 3836

TESTING POINTS	TEMPERATURE MEASURED IN °C			HUMIDITY MEASURED IN %RH		
	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE	CALIBRATION STANDARD	INSTRUMENT OUTPUT	ALLOWABLE RANGE
1	-38.9	-38.9	-38.3 ~ -39.4	71.4	71.5	71.3 ~ 71.5
2	-15.0	-15.0	-14.8 ~ -15.2	5.6	5.6	5.5 ~ 5.7
3	25.0	25.0	24.9 ~ 25.1	-	-	-
4	70.0	70.0	69.9 ~ 70.1	-	-	-
5	110.0	110.0	109.8 ~ 110.2	-	-	-

* Indicates out of tolerance condition

TSI Incorporated does hereby certify that the above described instrument conforms to the original manufacturer's specifications (not applicable to As Found data) and has been calibrated using standards whose accuracies are traceable to the National Institute of Standards and Technology within the limitations of NIST's calibration services or have been derived from accepted values of natural physical constants or have been derived by the ratio type of self calibration techniques. The calibration ratio for this instrument is at least 6.7:1 for barometric pressure and 3:1 for differential pressure. TSI's calibration system meets ISO-9001:2008 and complies with ISO 10012:2003, Quality Assurance Requirements for Measuring Equipment. This report may not be reproduced, except in full, unless permission for the publication of an approved abstract is obtained in writing from the calibration organization issuing this report.

Measurement Variable	System ID Number	Date Last Calibrated	Calibration Due Date
DC Voltage	E002798	06-24-10	12-24-11
DC Voltage	E002797	06-24-10	12-24-11
Pressure	E002173	06-16-10	12-16-10
Pressure	E002447	06-30-10	06-30-11

Calibration procedure used: 10000000787B

Thay Xiong
Calibrated By

Nov. 2, 2010

Calibration Date